

## PART 1 - GENERAL

Not used.

## PART 2 - PRODUCTS

Not used.

## PART 3 - EXECUTION

### 3.1 PROTECTION

#### 3.1.1 Roads and Walks

Keep roads and walks free of dirt and debris at all times.

#### 3.1.2 Shrubs

Protection shall be in accordance with Section 01575, "Temporary Environmental Controls."

#### 3.1.3 Utility Lines

Protect existing utility lines that are indicated to remain from damage. Notify the Contracting Officer immediately of damage to or an encounter with an unknown existing utility line. The Contractor shall be responsible for the repairs of damage to existing utility lines that are indicated or made known to the Contractor prior to start of clearing and grubbing operations. When utility lines which are to be removed are encountered within the area of operations, the Contractor shall notify the Contracting Officer in ample time to minimize interruption of the service. Refer to Section Section 01575, "Temporary Environmental Controls," for additional utility protection.

### 3.2 CLEARING

Shall consist of vegetation designated for removal, snags, brush, and rubbish occurring within the areas to be cleared. Cut off flush with or below the original ground surface roots, brush, and other vegetation in areas to be cleared, except for vegetation indicated or directed not to be removed.

### 3.3 GRUBBING

Remove and dispose of roots larger than 3 inches in diameter and matted roots from the indicated grubbing areas. Excavate this material together with logs, organic and metallic debris, brush, and refuse and remove to a depth of not less than 18 inches below the original soil surface in areas indicated to be grubbed and in areas indicated as construction areas under this contract. Fill depressions made by grubbing with suitable material and compact in accordance with the requirements specified in Section 02301, "Earthwork for Structures and Pavements," to make the new surface conform with the existing adjacent surface of the ground.

### 3.4 DISPOSAL OF CLEARED AND GRUBBED MATERIALS

#### 3.4.1 Nonsaleable Materials

Remove from the project site and dispose of off station.

END OF SECTION